


Daniel “Danny” Mayfield
Commissioner, District 1

Miguel M. Chavez
Commissioner, District 2

Robert A. Anaya
Commissioner, District 3



Kathleen Holian
Commissioner, District 4

Liz Stefanics
Commissioner, District 5

Katherine Miller
County Manager

October 10, 2014

SANTA FE COUNTY
IFB# 2015-0129-PW/PL
INSTALLATION OF ROADWAY
GUARDRAILS, BARRIER CABLE & COMPONENTS

ADDENDUM #1

Dear Bidders,

This addendum is issued to reflect the following immediately. It shall be the responsibility of interested bidders to adhere to any changes or revisions to the IFB as identified in this Addendum No. 1. This documentation shall become permanent and made part of the departmental files.

ATTACHMENT: REVISED BID SHEETS TO BE USED IN BID SUBMITTAL

ATTACHMENT: PRE-BID CONFERENCE SIGN IN SHEET

On October 6, 2014 Santa Fe County held the pre-bid conference for the above referenced Invitation for Bid (IFB). Listed below are questions asked at the conference and/or received via email.

Question #1- What are the types and sizes of projects that the County will be requiring under this Price Agreement?

Answer #1- Road construction projects will include new and replacement guardrails. Guardrail runs will vary in length from 25 to 1,000 feet. Also there will be repairs to guardrails due to accidental damage. Most of the projects will involve beam guardrail installation with ET 2000 end treatments and B-anchors.

Question #2- Item 44 & Item 45 are requiring a unit price of "EACH" for Traffic Control; can this be changed to "PER HOUR" as it will be difficult to give a unit price of "EACH" as guardrail installations can vary in the amount of time required to complete a project.

Answer #2- Yes, the unit price will be changed to per hour and this change is reflected in the attached **REVISED BID SHEETS** to be used in the bid submittal in place of the one found in the IFB.

Please add this Addendum #1 to the original bid documents and refer to bid documents, hereto as such. This and all subsequent addenda will become part of any resulting contract documents and have effects as if original issued. All other unaffected sections will have their original interpretation and remain in full force and effect.

Bidders are reminded that any questions or need for clarification must be addressed to Pamela Lindstam, Senior Procurement Specialist at plindsta@santafecountynm.gov.

ATTACHMENT 1

REVISED BID SHEETS TO BE USED IN BID SUBMITTAL

REVISED BID SHEETS
INSTALLATION OF ROADWAY GUARDRAILS,
BARRIER CABLE & COMPONENTS
IFB #2015-0129-PW/PL

Please offer your best price for all bid items based on the unit price indicated below to include all costs for labor, equipment, tools, materials, federal tax, permits, licenses, fees and any other items necessary to complete the services. Be advised that award may be made without discussion with Bidders.

Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
1	45	SF	Class A concrete repairs as specified by the Sq. Ft. – Repairs are for chipped-out concrete sections from wingwalls etc.		
2	1500	LF	Metal Barrier, W-Beam Installation		
3	20	LF	Cor-Ten W-Beam Metal Barrier Installation		
4	500	LF	Metal Barrier, Three Beam Installation		
5	20	LF	Cor-Ten Three Beam Metal Barrier Installation		
6	2	EA	Metal Barrier, Anchorage Type “A” Installation		
7	1	EA	Cor-Ten Type “A” Anchor Metal Barrier Installation		
8	2	EA	Type B End Anchorage for curved guardrail installation to include all parts, materials and labor		
9	1	EA	Cor-Ten Type “B” Anchor Metal Barrier Installation		

Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
10	1	EA	Metal Barrier, Anchorage Type "D" Installation, Buried in Backslope, per Standard Drawings		
11	100	LF	Curved Guardrail Installation, radius as specified by the County to include all parts, materials and labor		
12	20	LF	Cor-Ten Curved Guardrail Installation; radius as specified by the County to include all parts, materials and labor		
13	10	CY	Earthwork equipment compacting; to be determined by cross sections of excavated area		
14	2	CY	Guardrail Pad Installation		
15	3	EA	ET Plus Guardrail End Treatment-Type 1 50 foot, installed per manufacturer's recommendations and Standard Drawing, including prismatic sheeting on extruder head		
16	1	EA	ET Plus Guardrail End Treatment-Type 1 50 foot, installed per manufacturer's recommendations and Standard Drawing, including prismatic sheeting on extruder head (extruder head finished to match Con-Ten Rail)		
17	3	EA	ET Plus Guardrail End Treatment – Type 2 37 foot 6 inch, installed as per manufacturer's recommendations and Standard Drawings, including prismatic sheeting on extruder head		

Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
18	1	EA	ET Plus Guardrail End Treatment – Type 2 37 foot 6 inch, installed per manufacturer's recommendations and Standard Drawing, including prismatic sheeting on extruder head (extruder head finished to match Cor-Ten rail)		
19	3	EA	Fleat 350 Flared End Treatment – Type 2 installed per manufacturer's recommendations and Standard Drawing, including prismatic sheeting on extruder head		
20	1	EA	Fleat 350 Flared End Treatment – Type 2 installed per manufacturer's recommendations and Standard Drawing, including prismatic sheeting on extruder head (extruder head finished to match Cor-Ten rail)		
21	3	EA	SKT 350 Guardrail End Treatment – Type 1 installed per manufacturer's recommendations and Standard Drawing, including prismatic sheeting on extruder head		
22	1	EA	SKT 350 Guardrail End Treatment –Type 1 installed per manufacturer's recommendations and Standard Drawing, including prismatic sheeting on extruder head (extruder head finished to match Cor-Ten rail)		
23	500	LF	Installation of W-Beam Metal Barrier provided by Santa Fe County and delivered to site		
24	10	EA	Prismatic Grade Sheeting for Extruder Heads		

Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
25	500	LF	Removal of Salvageable Metal Barrier, including posts and components, stockpiled at directed by Santa Fe County		
26	200	LF	Remove and Rebuild existing Metal Barrier, Posts and Components as directed by Santa Fe County		
27	30	Hour	Sequential Flashing Arrows Flashing Directional Arrows as required by Santa Fe County		
28	20	LF	Three-Beam Metal Barriers Installation attaching transitions to Concrete Wall Barrier		
29	20	LF	Three-Beam Metal Barrier Installation attaching transitions to Bridge Railing		
30	25	LF	Nested Three-Beam Metal Barrier Installation		
31	30	LF	W-Beam Metal Barrier Installation attaching transitions to Bridge Railing		
32	500	FT	Wire Rope System Installation with Sleeved Posts (Trinity Cass) per manufacturer's recommendations		
33	8	EA	End Treatment Complete Installation for Wire Rope System with Sleeved Posts (Trinity Cass)		
34	200	FT	Maintenance of Wire Rope System with Sleeved Posts (Trinity Cass)		
35	5	EA	Repair of and Replacement		

			of Damaged Line Post Footing (Trinity Cass)		
Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
36	200	FT	Wire Rope System Installation with Sleeved Posts (Brifen) per manufacturer's recommendations		
37	8	EA	End Treatment Complete for Wire Rope System Installation with Sleeved Posts (Brifen)		
38	200	FT	Maintenance of Wire Rope System with Sleeved Posts (Brifen)		
39	5	EA	Repair of and Replacement of Damaged Line Post Footing (Brifen)		
40	200	EA	Wire Rope System Installation with Sleeved Posts (Safence) per manufacturer's recommendations		
41	8	EA	End Treatment Complete for Wire Rope System Installation with Sleeved Posts (Safence)		
42	200	FT	Maintenance of Wire Rope System with Sleeved Posts (Safence)		
43	5	EA	Repair of and Replacement of Damaged Line Post Footing (Safence)		
44	1	PER HOUR	Traffic Control – Two Lane Roadway with One-Lane Closure, Flagman and Pilot Car		
45	1	PER HOUR	Traffic Control – Inside Lanes/Median, Outside Lanes Operation for Multi-Lane Highways		

Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
46	100	Mile	Mobilization – one way, one-time travel mileage per work request as defined as continuous travel within the State of New Mexico by the shortest route from Contractor's designated base station (or entrance to the state from closest state line in the case of an out-of-state Contractor) to reach all jobsites in a single order and to be based upon map mileages. For requested delivery of removed materials to designated Santa Fe County yard, designated yard will be considered a work site for calculation purposes of the bid item. No payment will be made for Contractor's return to designated base station.		

All bid item amounts are exclusive of NM gross receipts tax

BID SUBMITTED BY:

COMPANY NAME: _____

NAME: _____

SIGNATURE: _____

TITLE: _____

EMAIL ADDRESS: _____

DATE: _____

ATTACHMENT 2

PRE-BID CONFERENCE

SIGN-IN SHEET

INSTALLATION OF ROADWAY GUARDRAILS, BARRIER CABLE & COMPONENTS

IFB #2015-0129-PW/PL

INSTALLATION OF ROADWAY GUARDRAILS, BARRIER CABLE & COMPONENTS

OCTOBER 6, 2014

10:30 AM (MDT)

[illegible]