

Henry P. Roybal
Commissioner, District 1

Anna Hansen
Commissioner, District 2

Robert A. Anaya
Commissioner, District 3



Anna T. Hamilton
Commissioner, District 4

Ed Moreno
Commissioner, District 5

Katherine Miller
County Manager

September 7, 2018

SANTA FE COUNTY
IFB# 2018-0288-PW/MAM
GUARDRAILS, BARRIER CABLE &
COMPONENTS

ADDENDUM #1

Dear Proponents,

This addendum is issued to reflect the following immediately. It shall be the responsibility of interested Offerors to adhere to any changes or revisions to the IFB as identified in this Addendum No. 1. This documentation shall become permanent and made part of the departmental files.

Pre Bid Agenda and Sign in Sheet
Attachment A: *REVISED BID SHEET*******

Question# 1: Could we possibly have a separate item for the leavout item itself? No posts or anything, just the actual installation of the leavout itself, this item would include labor and some tact oil to cover.

Answer# 1: We will add a bid item 11 (see attachment A REVISED BID SHEET) specific to this that will read as follows: "Post Leavouts if posts are restrained by rock, asphalt or concrete" per each post.

Question #2: The Type A anchor (items 6 & 7) as well as Type D anchor (Item 10) are obsolete and have not been installed in years. Could we have these removed from the bid? * along with these the new updated specs list the end anchors a little differently as you will notice the type b is now a "W beam end anchor" and the Type C is now a "Driveway End Anchor"

Answer# 2: **Yes. The Type A anchor (items 6 and 7) as well as Type D anchor (Item 10) are obsolete will be removed from the bid.**
Language referencing type B will be removed and replaced with “W Beam end anchor” (see item 6 in Attachment A REVISED BID SHEET)
Language referencing type C will be removed and replaced with “Driveway end anchor. (see item 7 in Attachment A REVISED BID SHEET)

Please add this Addendum #1 to the original proposal documents and refer to proposal documents, hereto as such. This and all subsequent addenda will become part of any resulting contract documents and have effects as if original issued. All other unaffected sections will have their original interpretation and remain in full force and effect. Responders are reminded that any questions or need for clarification must be addressed to Michelle A. Marmion, Senior Procurement Specialist at mmarmion@santafecountynm.gov

**GUARDRAILS, BARRIER CABLE & COMPONENTS
IFB #2018-0288-PW/MAM**

**PRE-BID CONFERENCE
WEDNESDAY, AUGUST 29, 2018
11:00 AM (MDT)**

INTRODUCTIONS

Contracting Agency: Santa Fe County Public Works

- Michelle A. Marmion Procurement Specialist Sr. Purchasing Division
- Johnny Baca Traffic Manager Public Works

Project Description

- Santa Fe County is requesting bids for the purpose of installation and/or repair of roadway guardrail, barrier cables and components to be used on County roads on an as needed basis. SFC Public Works is looking to award multiple (4) year contracts with eligible bidders.
- Guardrails are used throughout our transportation system hence its primary purpose is to prevent vehicles from leaving the roadway and striking a fixed object or terrain feature that is less forgiving than striking the barrier itself.

Bid Documents

- The bid documents are available by contacting Michelle A. Marmion, Procurement Specialist at (505) 992-6753, or by e-mail at mmarmion@santafecountynm.gov or by visiting our website at http://www.santafecountynm.gov/asd/current_bid_solicitations

Bid Information

- Basis of Award – Due to the County’s responsibility for various road maintenance and safety conditions on County roads, it would be in the best interest of the County to award multiple contracts to provide the required services for the various road projects.
- Last Day for Questions – Tuesday, September 4, 2018
- Addendum Issued– Friday, September 7, 2018
- Bid Schedule:

**Bid Opening: Wednesday, September 19, 2018
Location: Santa Fe County Purchasing Division, (Bokum Building,
Second Floor),
142 W. Palace Avenue, Santa Fe, N.M. 87501
Time: 2:00 PM (MDT)**

- Review and understand the terms & conditions, and the sample contract
- All bid forms must be completed and signed on page 24-40
- General contractors and subcontractors require CID Licenses. The license can be a GA-98.

- All contractors and subcontractors must be registered with the N.M. Department of Workforce Solutions for all work over \$60,000 on day of bid.
(Must be registered as “Active”)

Questions

ATTACHMENT A REVISED BID SHEET

******REVISED ******

BID SHEETS INSTALLATION OF ROADWAY GUARDRAILS, BARRIER CABLE & COMPONENTS IFB #2018-0288-PW/MAM

Modified date: 09/07/2018

Please offer your best price for all bid items based on the unit price indicated below to include all costs for labor, equipment, tools, materials, federal tax, permits, licenses, fees and any other items necessary to complete the services. Be advised that award may be made without discussion with Bidders.

Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
1	45	SF	Class A concrete repairs as specified by the Sq. Ft. – Repairs are for chipped-out concrete sections from wingwalls etc.		
2	1500	LF	Metal Barrier, W-Beam Installation		
3	20	LF	Cor-Ten W-Beam Metal Barrier Installation		
4	500	LF	Metal Barrier, Three Beam Installation		
5	20	LF	Cor-Ten Three Beam Metal Barrier Installation		
6	2	EA	W Beam end anchor		
7	1	EA	Driveway end anchor		

Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
8	100	LF	Curved Guardrail Installation, radius as specified by the County to include all parts, materials and labor		
9	20	LF	Cor-Ten Curved Guardrail Installation; radius as specified by the County to include all parts, materials and labor		
10	10	CY	Earthwork equipment compacting; to be determined by cross sections of excavated area		
11	500	EA	Post Leavouts if post are restrained by rock, asphalt, or concrete, per each post		
12	2	CY	Guardrail Pad Installation		
13	3	EA	ET Plus Guardrail End Treatment-Type 1 50 foot, installed per manufacturer's recommendations and Standard Drawing, including prismatic sheeting on extruder head		
14	1	EA	ET Plus Guardrail End Treatment-Type 1 50 foot, installed per manufacturer's recommendations and Standard Drawing, including prismatic sheeting on extruder head (extruder head finished to match Con-Ten Rail)		
15	3	EA	ET Plus Guardrail End Treatment – Type 2 37 foot 6 inch, installed as per manufacturer's recommendations and		

			Standard Drawings, including prismatic sheeting on extruder head		
--	--	--	--	--	--

Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
16	1	EA	ET Plus Guardrail End Treatment – Type 2 37 foot 6 inch, installed per manufacturer’s recommendations and Standard Drawing, including prismatic sheeting on extruder head (extruder head finished to match Cor-Ten rail)		
17	3	EA	Fleat 350 Flared End Treatment – Type 2 installed per manufacturer’s recommendations and Standard Drawing, including prismatic sheeting on extruder head		
18	1	EA	Fleat 350 Flared End Treatment – Type 2 installed per manufacturer’s recommendations and Standard Drawing, including prismatic sheeting on extruder head (extruder head finished to match Cor-Ten rail)		
19	3	EA	SKT 350 Guardrail End Treatment – Type 1 installed per manufacturer’s recommendations and Standard Drawing, including prismatic sheeting on extruder head		
20	1	EA	SKT 350 Guardrail End Treatment –Type 1 installed per manufacturer’s recommendations and Standard Drawing, including prismatic sheeting on extruder head (extruder head finished to match Cor-Ten rail)		
21	500	LF	Installation of W-Beam Metal Barrier provided by Santa Fe County and delivered to site		

22	10	EA	Prismatic Grade Sheeting for Extruder Heads		
----	----	----	---	--	--

Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
23	500	LF	Removal of Salvageable Metal Barrier, including posts and components, stockpiled at directed by Santa Fe County		
24	200	LF	Remove and Rebuild existing Metal Barrier, Posts and Components as directed by Santa Fe County		
25	30	Hour	Sequential Flashing Arrows Flashing Directional Arrows as required by Santa Fe County		
26	20	LF	Three-Beam Metal Barriers Installation attaching transitions to Concrete Wall Barrier		
27	20	LF	Three-Beam Metal Barrier Installation attaching transitions to Bridge Railing		
28	25	LF	Nested Three-Beam Metal Barrier Installation		
29	30	LF	W-Beam Metal Barrier Installation attaching transitions to Bridge Railing		
30	500	FT	Wire Rope System Installation with Sleeved Posts (Trinity Cass) per manufacturer's recommendations		
31	8	EA	End Treatment Complete Installation for Wire Rope System with Sleeved Posts (Trinity Cass)		

32	200	FT	Maintenance of Wire Rope System with Sleeved Posts (Trinity Cass)		
33	5	EA	Repair of and Replacement of Damaged Line Post Footing (Trinity Cass)		
Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
34	200	FT	Wire Rope System Installation with Sleeved Posts (Brifem) per manufacturer's recommendations		
35	8	EA	End Treatment Complete for Wire Rope System Installation with Sleeved Posts (Brifem)		
36	200	FT	Maintenance of Wire Rope System with Sleeved Posts (Brifem)		
37	5	EA	Repair of and Replacement of Damaged Line Post Footing (Brifem)		
38	200	EA	Wire Rope System Installation with Sleeved Posts (Safence) per manufacturer's recommendations		
39	8	EA	End Treatment Complete for Wire Rope System Installation with Sleeved Posts (Safence)		
40	200	FT	Maintenance of Wire Rope System with Sleeved Posts (Safence)		
41	5	EA	Repair of and Replacement of Damaged Line Post Footing (Safence)		
42	1	EA	Traffic Control – Two Lane Roadway with One-Lane Closure, Flagman and Pilot Car		

43	1	EA	Traffic Control – Inside Lanes/Median, Outside Lanes Operation for Multi-Lane Highways		
----	---	----	--	--	--

Item	Approx. Qty.	Unit	Article and Description	Unit Price \$	Unit Price Written in Word
44	100	Mile	Mobilization – one way, one-time travel mileage per work request as defined as continuous travel within the State of New Mexico by the shortest route from Contractor’s designated base station (or entrance to the state from closest state line in the case of an out-of-state Contractor) to reach all jobsites in a single order and to be based upon map mileages. For requested delivery of removed materials to designated Santa Fe County yard, designated yard will be considered a work site for calculation purposes of the bid item. No payment will be made for Contractor’s return to designated base station.		

All bid item amounts are exclusive of NM gross receipts tax

BID SUBMITTED BY:

COMPANY NAME: _____

NAME: _____

SIGNATURE: _____

TITLE: _____

EMAIL ADDRESS: _____

DATE: _____