


Henry P. Roybal
Commissioner, District 1

Anna Hansen
Commissioner, District 2

Robert A. Anaya
Commissioner, District 3



Anna T. Hamilton
Commissioner, District 4

Ed Moreno
Commissioner, District 5

Katherine Miller
County Manager

May 31, 2017

SANTA FE COUNTY
RFP# 2017-0281-PW/KE
CONSTRUCTION FOR THE SANTA FE RIVER
GREENWAY PROJECT
ADDENDUM #3

Dear Proponents,

This addendum is issued to reflect the following immediately. It shall be the responsibility of interested Offerors to adhere to any changes or revisions to the RFP as identified in this Addendum No. 3. This documentation shall become permanent and made part of the departmental files.

ATTACHMENT: REVISED BID SHEETS (8 pages)

ATTENTION!! THE DUE DATE FOR PROPOSALS HAS BEEN EXTENDED!

All Proposals will be due in the Purchasing Office at 142 W. Palace Ave., Santa Fe NM, no later than Thursday, JUNE 8, 2017 AT 2:00PM (MDT)!

*** Please see Bid Item 56; an allowance of \$10,000.00 has been added along with specific directions for the existing well.

Please add this Addendum #3 to the original bid documents and refer to bid documents, hereto as such. This and all previous and subsequent addenda will become part of any resulting contract documents and have effects as if original issued. All other unaffected sections will have their original interpretation and remain in full force and effect.

Bidders are reminded that any questions or need for clarification must be addressed to Karen K. Emery, Senior Procurement Specialist at kkemery@santafecountynm.gov.

REVISED BID SHEET
(FROM ADDENDUM #3)
SANTA FE RIVER GREENWAY PROJECT

BID ITEM	DESCRIPTION	UNIT	QTY	UNIT COST (\$)	EXTENDED PRICE (\$)
1	SITE CLEAR & GRUB	AC	18		
2	SURFACE DEBRIS REMOVAL; SORT AND STOCKPILE USABLE CONCRETE SLABS, BOULDERS, & COBBLE; DISPOSE OF UNSUITABLE MATERIAL	CY	11,000		
3	UNCLASSIFIED EXCAVATION, INCL. PLACEMENT AND COMPACTION TO NEW GRADES, CIP	CY	53,600		
4	HAUL AND DISPOSE OF EXCESS CUT OFFSITE, IF REQUIRED	CY	13,300		
5	TRAIL & SHOULDER SUBGRADE PREPARATION	SY	8,610		
7	GRADING <2' DEPTH FOR CARLOS RAEL STORMWATER BASINS	SY	160		
8	GRADED GRAVEL FILTER	CY	1,949		

BID ITEM	DESCRIPTION	UNIT	QTY	UNIT COST (\$)	EXTENDED PRICE (\$)
9	COMPACTED BASE COURSE SHOULDER, 'SANTA FE BROWN', 6" DEPTH	SY	2,460		
10	MODULAR CMU RETAINING WALL, CIP, INCLUDING CRUSHED GRAVEL FOOTING AND BACKFILL (WALL FACE AREA)	SF	360		
11	MODULAR CMU PRIVACY WALL, 6' HIGH, CIP, INCLUDING CRUSHED GRAVEL FOOTING (WALL FACE AREA)	SF	2,280		
12	STRUCTURAL CONCRETE BANK PROTECTION/RETAINING WALL, CLASS A, WITH INTEGRAL COLOR, EMBEDDED GRAVEL ACCENTS, AND SAND BLAST FINISH, INCLUDING SUBGRADE PREP AND BACKFILL, CIP	CY	690		
13.1	STRUCTURAL CONCRETE BRIDGE ABUTMENTS & RETAINING WALLS, CLASS AA, WITH FORM LINER AND CLASS 1 FINISH, INCLUDING BACKFILL AND COMPACTION, CIP	CY	20		
13.2	STRUCTURAL CONCRETE BRIDGE PILES, INCLUDING REINFORCING STEEL, FORMWORK, BACKFILL AND COMPACTION, CIP	CY	17		
14	CLASS D CONCRETE CURB AND GUTTER	CY	2.5		

BID ITEM	DESCRIPTION	UNIT	QTY	UNIT COST (\$)	EXTENDED PRICE (\$)
15	SUBSTRUCTURE CONCRETE FOOTING, CLASS A, INCLUDING SUBGRADE PREP AND BACKFILL, CIP	CY	260		
16	PRE-ENGINEERED BRIDGE, 10' X 110', CIP, INCLUDING DECK AND GEOTECH INVESTIGATION	EA	1		
17	18" CMP CULVERT PIPE, INSTALLED	LF	210		
18	18" CULVERT PIPE END SECTION, INSTALLED	EA	18		
19	30" CMP CULVERT PIPE, INSTALLED, INCLUDING CONNECTOR	LF	16		
20	30" CULVERT PIPE END SECTION, INSTALLED	EA	1		
21	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	1		
22	REMOVAL OF EXISTING ROAD SURFACING	SY	1,400		

BID ITEM	DESCRIPTION	UNIT	QTY	UNIT COST (\$)	EXTENDED PRICE (\$)
23	CLASS B BASALT RIPRAP, IMPORTED FOR RUNDOWNS AND SWALES, AS NEEDED, CIP	TON	1,367		
24	CLASS C BASALT RIPRAP, IMPORTED FOR GRADE CONTROL STRUCTURE APRONS, CIP	CY	620		
25	BOULDER GRADE CONTROL STRUCTURE, GROUTED, CIP INCLUDING GROUT	CY	2,671		
26	BOULDER DEFLECTOR & BANK PROTECTION STRUCTURES, CIP	CY	2,204		
27	CLASS G ROCK SLOPE PLATING, CIP (USING ROCK COLLECTED ON SITE AND/OR IMPORTED BASALT)	SY	1,080		
28	COLLECT, STOCKPILE, AND INSTALL BASALT COBBLE &/OR SMALL BOULDERS, 6-18", FOR SCOUR BASINS, CIP	CY	1,150		
29	STACKED CONCRETE SLAB RUNDOWN, CIP (FACE AREA)	SF	500		
30	PLACE USABLE, STOCKPILED CONCRETE SLABS, BOULDERS & COBBLE IN CHANNEL SCOURS	CY	2,756		

BID ITEM	DESCRIPTION	UNIT	QTY	UNIT COST (\$)	EXTENDED PRICE (\$)
31	BOULDER SILL, CIP (SINGLE LAYER OF BOULDERS)	LF	2,520		
32	GABION FOOTER, INCLUDING STONE/CONC. RUBBLE FILL, CIP	CY	28		
33	SWPPP MANAGEMENT	LS	1		
34	SWPPP IMPLEMENTATION	LS	1		
35	3-BAR PEDESTRIAN/BICYCLE RAILING, UNPAINTED	LF	660		
36	REMOVE AND REBUILD EXISTING ROW/WIRE FENCE	LF	600		
37	CONCRETE TRAIL SURFACE, TINTED 'OATMEAL BUFF', 6" THICKNESS	SY	6,150		
38	TRAFFIC CONTROL	LS	1		

BID ITEM	DESCRIPTION	UNIT	QTY	UNIT COST (\$)	EXTENDED PRICE (\$)
39	CONSTRUCTION MOBILIZATION/DEMOBILIZATION	LS	1		
40	PROTECTION OF THE PROJECT FROM WATER	LS	1		
41	NATIVE SEEDING, CLASS C	AC	18		
42	TREES: COTTONWOOD FROM CONTAINER STOCK, INSTALLED	EA	142		
43	MANHOLE ADJUSTMENT	EA	3		
44	UTILITY RELOCATION ALLOWANCE	ALLOW	1	\$10,000	\$10,000
45	WILLOW POLE PLANTINGS (5 STEMS PER HOLE), INSTALLED, PER HOLE	EA	3,000		
46	WILLOW WATTLES, FABRICATE AND INSTALL	LF	1,800		

BID ITEM	DESCRIPTION	UNIT	QTY	UNIT COST (\$)	EXTENDED PRICE (\$)
47	REMOVABLE LOCKING BOLLARD (GUARD POST)	EA	2		
48	2' TO 4' SEATING BOULDER, CIP	EA	18		
49	ALUMINUM PANEL SIGN	SF	30		
50	INSTALL UPRIGHT PANEL SIGN (PANEL, POSTS, AND HARDWARE PROVIDED BY COUNTY)	EA	1		
51	STEEL SIGN POST AND BASE POST, CIP	LF	88		
52	WOOD SIGN POST WITH STEEL BASE, INSTALLED	EA	5		
53	CONST. STAKING BY CONTRACTOR	LS	1		
54	POST-CONSTRUCTION PLANS (RECORD DRAWINGS)	LS	1		

BID ITEM	DESCRIPTION	UNIT	QTY	UNIT COST (\$)	EXTENDED PRICE (\$)
55	QC/QA TESTING	ALLOW	1	\$10,000	\$10,000
56	REMOVE ROCK COVERING EXISTING WELL, INSPECT THE CASING CONDITION AT THE SURFACE, FURNISH AND INSTALL A SECURE METAL CAP AND PLACE A 4.5 FOOT SQUARE BY 4-INCH THICK CONCRETE SEAL AROUND THE WELL HEAD.	ALLOW	1	\$10,000	\$10,000
BASE BID SUBTOTAL WRITTEN IN NUMBERS:				BASE BID SUBTOTAL WRITTEN IN WORDS:	
\$ _____					