


Henry P. Roybal
Commissioner, District 1

Anna Hansen
Commissioner, District 2

Robert A. Anaya
Commissioner, District 3



Anna T. Hamilton
Commissioner, District 4

Ed Moreno
Commissioner, District 5

Katherine Miller
County Manager

March 1, 2018

SANTA FE COUNTY
IFB NO. 2018-0247-PW/MM
SURFACE AND DRAINAGE ROAD IMPROVEMENTS FOR VARIOUS ROADS

ADDENDUM NO. 2

Dear Proponents,

This addendum is issued to reflect the following immediately. It shall be the responsibility of interested bidders to adhere to any changes or revisions to the IFB as identified in this Addendum No. 2. This documentation shall become permanent and made part of the departmental files.

Attachments: Mandatory Pre-Bid Sign in Sheet & Agenda

Clarification No. 1: **Santa Fe County's preference is to utilize Hot Mix if the budget allows. However, the basis of award is the lowest responsive bidder on Double Layer Chip Seal. We urge bidders to provide the best price on both applications.**

Question No. 1: Who is responsible for the disposal of culverts and cattle guards?

Answer No. 1: **The awarded contractor is responsible for delivering the cattle guards to the Santa Fe County Maintenance District Yard No. 5 located at 685B Highway 472 in Stanley. The contractor is also responsible for removing the culverts from project sites and disposing at a landfill and/or metal salvage yard.**

Question No. 2: What is the budget for this project?

Answer No. 2: **The County is not releasing the budget at this time. However, Santa Fe County's estimate is \$2.9 million.**

Please add this Addendum No. 2 to the original bid documents and refer to bid documents, hereto as such. This and all subsequent addenda will become part of any resulting contract documents and have effects as if original issued. All other unaffected sections will have their original interpretation and remain in full force and effect. Responders are reminded that any questions or need for clarification must be addressed to Maricela Martinez, Senior Procurement Specialist at mcmartinez@santafecountnm.gov.



MANDATORY PRE BID CONFERENCE & SITE VISIT

IFB #2018-0247-PW/MM


SURFACE AND DRAINAGE ROAD IMPROVEMENTS FOR VARIOUS COUNTY ROADS

FEBRUARY 22, 2018

1:30PM

NAME	COMPANY	TELEPHONE	E-MAIL ADDRESS
Michelle Martinez	GM Emulsion, LLC	505 471-9981	Michelle.G@emulsion.com
Thomas Howells	AVI INC.	505-242-4840 505-242-0108	townandaviinc.net
Neil Jackson	Mountain States Constructors, Inc.	505-292-0105	neil@msconstr.com
Mike Brown	Mountain States Constructors, Inc.	505-292-0105	mbrown@msconstructors.com
Gabriel Alvarez	GME	575-840-9709	gabriel@gmeemulsion.com
TUG LEEDER	RL LEEDER	473-1360	TUG@RLLEEDER.COM
Diego Gomez	SFC	490-2825	dgomez@santafecountynm.gov
Robert Martinez	SFC	992-3015	robertz@santafecountynm.gov
D. Scott Smith	SFC	986-2416	DSSMITA@SANTAFECOUNTYNM.GOV
Maricela Martinez	SFC purchasing	992-9804	mmartinez@santafecountynm.gov
LAWRENCE IMPRESCIA	SFC	490-2134	l.cimprescia@santafecountynm.gov

✓ indicated attendance at both Pre Bid and Site Visit.



**MANDATORY PRE-BID CONFERENCE & SITE VISIT
IFB# 2018-0247-PW/MM
SURFACE AND DRAINAGE ROAD IMPROVEMENTS
FOR VARIOUS COUNTY ROADS
FEBRUARY 22, 2018**

INTRODUCTIONS

Contracting Agency: Santa Fe County

- | | | |
|----------------------|----------------------------|--------------------------------|
| • Maricela Martinez | Procurement Specialist Sr. | Purchasing Division |
| • Daniel Scott Smith | Project Manager | Public Works/Project Division |
| • Diego Gomez | Projects Engineer | Public Works/Projects Division |

Project Information

- Santa Fe County is requesting bids from licensed, qualified contractors for road improvements to various County roads.
- **This project has a mandatory completion date of August 31, 2018.** The mandatory completion date for this contract is August 31, 2018 to commence on the date Notice to Proceed is granted or as directed by Santa Fe County. There will be no extensions for any reason.
- Liquidated Damages: \$2500 per each working day. that expires after the date of substantial completion until substantial completion is achieved and a certificate of Substantial Completion is issued by the County.

Bid Documents

- Bid Documents including specifications and plans are available by accessing our website at https://santafecountynm.gov/asd/current_bid_solicitations or contacting Maricela Martinez by telephone (505) 992-9864, or by email mcmartinez@santafecountynm.gov.
- Carefully read all bid documents for requirements, terms & conditions, including the sample contract.
- All bid forms must be completed, signed and included in the bid submittal.
If any of these requirements have not be met, the bid may be disqualified and deemed non-responsive

- General Contractors and Subcontractors require the appropriate CID licensure for work performed.
- All contractors and subcontractors must be registered with the N.M. Department of Workforce Solutions for all work over \$60,000. **(All contractors and subcontractors must be registered as “Active” on day of bid.)**
- Last Day for Questions – Tuesday, February 27, 2018, email questions to Maricela Martinez at mcmartinez@santafecountynm.gov **(Please do not email any other County staff and/or engineer.)**
- All Subcontractors must be listed on the subcontractors listing form.
- Addendum Issued- Thursday, March 1, 2018 by close of business *(Only questions answered by formal written addenda will be binding. Oral and other interpretations or clarifications will be without legal effect.)*
- Basis of Award: The lowest, responsive base bid amount.
- The awarded Contractor will be required to register all active subcontractors on the State of New Mexico Workforce Solutions website.
- **Bid Opening:**
 - Date:** March 12, 2018
 - Location:** Santa Fe County Purchasing Division
142 W. Palace Avenue (2nd floor, Bokum Bldg)
 - Time:** 2:00PM
- Late bids will not be accepted.
- This is a Mandatory pre-bid conference & site visit, only those contractors in attendance can bid on this project.
- Questions

Culvert Listing
White Lakes Road - 32,200 lf

Culvert Location	Culvert Length (ft)
21" x 15" Arch CMP Driveway #151AB	40
21" x 15" Arch CMP Driveway .9 mile	30
21" x 15" Arch CMP Driveway #210	40
21" x 15" Arch CMP Driveway #240	40
21" x 15" Arch CMP Driveway Gate @ 2.4 miles	40
21" x 15" Arch CMP Driveway #273	40
21" x 15" Arch CMP Driveway #321	40
21" x 15" Arch CMP Driveway #333AB	40

21" x 15" Arch CMP Driveway #377	40
21" x 15" Arch CMP Driveway #533	50
21" x 15" Arch CMP Driveway/Gate @ 5.7 miles	40
28" x 20" Arch CMP Across White Lakes Rd @ .1 miles	50(2)
28" x 20" Arch CMP Across White Lakes Rd @ .6 mile	50(2)
28" x 20" Arch CMP Across White Lakes Rd @ .75 mile	50
28" x 20" Arch CMP Across White Lakes Rd @ 2.7 mile	50
28" x 20" Arch CMP Across White Lakes Rd @ 2.9 mile	50
28" x 20" Arch CMP Across White Lakes Rd @ 3.7 mile	50
28" x 20" Arch CMP @ Kinsell Rd. SFC41	50
28" x 20" Arch CMP Across White Lakes Rd @ 5.0 mile	50
42"x29" Arch CMP Across White Lakes Rd. @ .33 miles	50
42"x29" Arch CMP Across White Lakes Rd. @ 3.3 miles	50(2)
42"x29" Arch CMP Across White Lakes Rd. @ 4.1 mile	50(2)
42"x29" Arch CMP Across White Lakes Rd. @ 4.6 miles	50(2)
42"x29" Arch CMP Across White Lakes Rd. @ 5.9 miles	50(3)
Total Length 21" x 15" Arch CMP	440
Total Length 28" x 20" Arch CMP	550
Total Length 42" x 29" Arch CMP	450

Simmons Road - 5,280 lf

Culvert Location	Culvert Length (ft)
21" x 15" Arch CMP Driveway #24	40
Total Length 21" x 15" Arch Corrugated Metal Pipe	40

County Road 12B - 13,900 lf

Culvert Location	Culvert Length (ft)
21" x 15" Arch CMP Driveway @ 1.1	40
21" x 15" Arch CMP Driveway #574	40
21" x 15" Arch CMP Driveway #579	40

21" x 15" Arch CMP Driveway #613AB	40
21" x 15" Arch CMP Driveway @ 2.3 miles	40(2)
28"x20" Arch CMP Across B Anaya @ 0.2 mile	50
28"x20" Arch CMP Across B Anaya @ 0.6 mile	50
28"x20" Arch CMP Across B Anaya @ 0.9 mile	50(2)
28"x20" Arch CMP Across B Anaya @ 1.0 mile	50(2)
28"x 20" Arch CMP Across B Anaya @ 1.4 mile	50(2)
28"x 20" Arch CMP Across B Anaya @ 2.6 mile	50(3)
42"x 29" Arch CMP Across B Anaya @ 1.6 mile	50(2)
42"x 29" Arch CMP Across B Anaya @ 2.4 mile	50(2)

Total Length 21" x 15" Arch Corrugated Metal Pipe 240
Total Length 28" x 20" Arch Corrugated Metal Pipe 550
Total Length 42" x 29" Arch Corrugated Metal Pipe 200

Drake Road - 3,240 lf

Culvert Location	Culvert Length (ft)
21" x 15" Arch CMP Driveway #14	40
21" x 15" Arch CMP Driveway #29	40
21" x 15" Arch CMP Driveway #34	40
21" x 15" Arch CMP Driveway #47	40
21" x 15" Arch CMP Driveway #50	40(2)
28" x 20" Arch CMP @ Bradley Court	50
35" x 24 " Arch CMP Across Drake @ .2 miles	50 (2)
42" x 29" Arch CMP Across Drake @ .4 miles	50 (2)

Total Length 21" x 15" Arch Corrugated Metal Pipe 240
Total Length 28" x 20" Arch Corrugated Metal Pipe 50
Total Length 35" x 24" Arch Corrugated Metal Pipe 100
Total Length 42" x 29" Arch Corrugated Metal Pipe 100

King Farm Road - 16,200 lf

Culvert Location	Culvert Length (ft)
21" x 15" Arch CMP Driveway @ .1 mile	50
21" x 15" Arch CMP Driveway/Gate @ .3 miles	50
21" x 15" Arch CMP Driveway/Gate @ .6 miles	50
21" x 15" Arch CMP Driveway/Gate @ .7 miles	40
21" x 15" Arch CMP Driveway/Fields @ 1.0 miles	60(2)
21" x 15" Arch CMP Driveway/Fields @ 1.3 miles	50 & 60
21" x 15" Arch CMP Driveway #164	40
21" x 15" Arch CMP Driveway/Fields @1.5 miles	50(2)
21" x 15" Arch CMP Driveway/Fields @1.6 miles	50
21" x 15" Arch CMP Driveway/Fields @1.8 miles	40(2)
21" x 15" Arch CMP Driveway/Fields @1.9 miles	50(2)
21" x 15" Arch CMP Driveway #93AB	50
21" x 15" Arch CMP Driveway #88	40
21" x 15" Arch CMP Driveway #82	50
21" x 15" Arch CMP Driveway #73	40
21" x 15" Arch CMP Driveway #58	40
28" x 20" Arch CMP Diamond Rd & King Farm @ 2.4 miles	50
21" x 15" Arch CMP Across King Farm - 2.5 mile	50(2)
42" x 29" Arch CMP Across King Farm @ .1 miles	50
42" x 29" Arch CMP Across King Farm @ 1.5 miles	50
42" x 29" Arch CMP Across King Farm @ 1.7 miles	50(2)
Total Length 21" x 15" Arch CMP	1110
Total Length 28" x 20" Arch CMP	50
Total Length 42" x 29" Arch CMP	200