

Attachment B

SANTA FE COUNTY

PUBLIC WORKS DEPARTMENT

CR-54 LOS PINOS ROAD ALL WEATHER CROSSING

IFB No. 2025-0258

ITEM#	BID ITEM	DESCRIPTION	UNIT	UNIT PRICE	TOTAL QTY	EXTENSION
1	201000	CLEARING AND GRUBBING	LS		1	
2	203000	UNCLASSIFIED EXCAVATION	CY		4,000	
3	203100	BORROW	CY		2,000	
4	203211	UNSTABLE SUBGRADE STABILIZATION	SY		420	
5	207000	SUBGRADE PREPARATION	SY		4,600	
6	210002	MAJOR STRUCTURE EXCAVATION	CY		1,300	
7	210003	MAJOR STRUCTURE BACKFILL	CY		300	
8	213000	OBLITERATING OLD ROAD	MILE		0.161	
9	303000	BASECOURSE	TON		1,320	
10	405000	DETOUR PAVEMENT CONSTRUCTION	SY		3,100	
11	407000	ASPHALT MATERIAL FOR TACK COAT	TON		2	
12	408100	PRIME COAT MATERIAL	TON		8	
13	416104	MINOR PAVING TYPE I, HMA SP-IV	TON		900	
15	511030	STRUCTURAL CONCRETE, CLASS AA	CY		470	
16	511200	STRUCTURAL CONCRETE, CLASS A-4"	SY		100	
17	540060	REINFORCING BARS GRADE 60	LB		129,000	
18	570024	24" CULVERT PIPE	LF		54	
19	570025	24" CULVERT PIPE END SECTION	EACH		1	
20	570154	24"S X 18"R (NOMINAL) CULVERT PIPE ARCH	LF		30	
21	570155	24"S X 18"R (NOMINAL) CULVERT PIPE ARCH END SECTION	EACH		2	
22	570170	64"SX43"R STORM DRAIN CULVERT PIPE ARCH	LF		240	
23	570171	64"SX43"R (NOMINAL) CULVERT PIPE ARCH END SECTION	EACH		8	
24	570170	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS		1	
25	570171	REMOVAL OF SURFACING	LS		1	
26	601000	RIPRAP CLASS A	CY		150	
27	601100	CHECK DAM TYPE II	LF		160	
28	602000	COMPOSTED MULCH SOCKS	LF		2,400	
29	603221	SWPPP PLAN PREPARATION AND MAINTENANCE	LS		1	
30	603262	SINGLE FACE W-BEAM GUARDRAIL	LF		325	

31	603281	END TREATMENT TL-2 END TERMINAL	EACH		4	
32	606001	TRANSITION METAL BARRIER TO RIGID BARRIER	EACH		4	
33	606052	CONCRETE WALL BARRIER 42"	LF		240	
34	606062	TCWB RETAINED BY THE CONTRACTOR (20')	LF		520	
35	606542	BARBED WIRE FENCE 4'	LF		470	
36	606710	HEADER CURB	LF		155	
37	607004	TRAFFIC CONTROL MANAGEMENT	LS		1	
38	609200	MOBILIZATION	LS		1	
39	618000	MEDIAN DROP INLET TYPE I (RURAL) H=0'0" TO 3'0"	EACH		1	
40	621000	CURB DROP INLET TYPE II-B, 0' TO 4'	EACH		2	
41	623011	CLASS C SEEDING	ACRE		1	
42	623312	PANEL SIGNS	SF		130	
43	632020	REMOVE AND RESET TRAFFIC SIGN	EACH		1	
44	701000	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	LF		300	
45	701031	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	LS		1	
46	701100	OBJECT MARKER TYPE 3	EACH		8	
47	702810	RETROREFLECTORIZED PAINTED MARKINGS 4"	LF		13,200	
48	703003	REMOVABLE MARKING TAPE 4"	LF		3,500	
49	704000	VEHICULAR IMPACT ATTENUATOR UNIT - WORK ZONES	EACH		2	
50	704100	CONSTRUCTION STAKING BY CONTRACTOR	LS		1	
51	720060	POST CONSTRUCTION PLANS	LS		1	

Total Exclusive of NM GRT

Total written in words