

Attachment B

SANTA FE COUNTY						
PUBLIC WORKS DEPARTMENT						
CR-54 LOS PINOS ROAD ALL WEATHER CROSSING						
IFB #2025-0258-PW/DK						
ITEM#	BID ITEM	DESCRIPTION	UNIT	UNIT PRICE	TOTAL QTY	EXTENSION
1	201000	CLEARING AND GRUBBING	LS		1	
2	203000	UNCLASSIFIED EXCAVATION	CY		4,000	
3	203100	BORROW	CY		2,000	
4	203211	UNSTABLE SUBGRADE STABILIZATION	SY		420	
5	207000	SUBGRADE PREPARATION	SY		4,600	
6	210002	MAJOR STRUCTURE EXCAVATION	CY		1,300	
7	210003	MAJOR STRUCTURE BACKFILL	CY		300	
8	213000	OBLITERATING OLD ROAD	MILE		0.161	
9	303000	BASECOURSE	TON		1,320	
10	405000	DETOUR PAVEMENT CONSTRUCTION	SY		3,100	
11	407000	ASPHALT MATERIAL FOR TACK COAT	TON		2	
12	408100	PRIME COAT MATERIAL	TON		8	
13	416104	MINOR PAVING TYPE I, HMA SP-IV	TON		900	
15	511030	STRUCTURAL CONCRETE, CLASS AA	CY		470	
16	511200	STRUCTURAL CONCRETE, CLASS A-4"	SY		100	
17	540060	REINFORCING BARS GRADE 60	LB		129,000	
18	570024	24" CULVERT PIPE	LF		54	
19	570025	24" CULVERT PIPE END SECTION	EACH		1	
20	570042	42' CULVERT PIPE	LF		120	
21	570043	42" CULVERT PIPE END SECTION	EACH		4	
22	570154	24"S X 18"R (NOMINAL) CULVERT PIPE ARCH	LF		30	
23	570155	24"S X 18"R (NOMINAL) CULVERT PIPE ARCH END SECTION	EACH		2	
24	570XXX	64" SX43"R STORM DRAIN CULVERT PIPE ARCH	LF		240	
25	570XXX	64" SX43"R (NOMINAL) CULVERT PIPE ARCH END SECTION	EACH		8	
26	601000	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS		1	
27	601100	REMOVAL OF SURFACING	LS		1	
28	602000	RIPRAP CLASS A	CY		150	
29	603221	CHECK DAM TYPE II	LF		160	
30	603262	COMPOSTED MULCH SOCKS	LF		2,400	
31	603281	SWPPP PLAN PREPARATION AND MAINTENANCE	LS		1	
32	606001	SINGLE FACE W-BEAM GUARDRAIL	LF		325	
33	606052	END TREATMENT TL-2 END TERMINAL	EACH		4	
34	606062	TRANSITION METAL BARRIER TO RIGID BARRIER	EACH		4	
35	606542	CONCRETE WALL BARRIER 42"	LF		240	
36	606710	TCWB RETAINED BY THE CONTRACTOR (20')	LF		520	
37	607004	BARBED WIRE FENCE 4'	LF		470	
38	609200	HEADER CURB	LF		155	
39	618000	TRAFFIC CONTROL MANAGEMENT	LS		1	
40	621000	MOBILIZATION	LS		1	
41	623011	MEDIAN DROP INLET TYPE I (RURAL) H=0'0" TO 3'0"	EACH		1	
42	623312	CURB DROP INLET TYPE II-B, 0' TO 4'	EACH		2	
43	632020	CLASS C SEEDING	ACRE		1	
44	701000	PANEL SIGNS	SF		130	
45	701031	REMOVE AND RESET TRAFFIC SIGN	EACH		1	
46	701100	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	LF		300	
47	702810	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	LS		1	
48	703003	OBJECT MARKER TYPE 3	EACH		8	
49	704000	RETROREFLECTORIZED PAINTED MARKINGS 4"	LF		13,200	
50	704100	REMOVABLE MARKING TAPE 4"	LF		3,500	
51	720060	VEHICULAR IMPACT ATTENUATOR UNIT - WORK ZONES	EACH		2	
52	801000	CONSTRUCTION STAKING BY CONTRACTOR	LS		1	
53	802000	POST CONSTRUCTION PLANS	LS		1	

Total Exclusive of NM GRT

Total written in words