

**ATTACHMENT B**

**AVENIDA VISTA GRANDE BRIDGE RECONSTRUCTION PROJECT**

**BASE BID FORM**

LINE ITEM	ITEM#	ITEM DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	201000	CLEARING AND GRUBBING	LS	\$9,315.00	1	\$9,315.00
2	203000	UNCLASSIFIED EXCAVATION	C.Y.	\$46.75	90	\$4,207.50
3	207000	SUBGRAOE PREPARATION	S.Y.	\$45.00	100	\$4,500.00
4	210002	MAJOR STRUCTURE EXCAVATION	C.Y.	\$63.00	130	\$8,190.00
5	210003	MAJOR STRUCTURE BACKFILL	C.Y.	\$210.00	100	\$21,000.00
6	303160	BASE COURSE 6"	S.Y.	\$680.00	60	\$40,800.00
7	408100	PRIME COAT MATERIAL	TON	\$7,200.00	1	\$7,200.00
8	417000	MISCELLANEOUS PAVING	S.Y.	\$180.00	100	\$18,000.00
g	511030	STRUCTURAL CONCRETE, CLASS AA	C.Y.	\$1,580.00	35	\$55,300.00
10	532000	PENETRATING WATER REPELLENT TREATMENT	S.Y.	\$13.00	960	\$12,480.00
11	533000	REPAIR OF CONCRETE STRUCTURES	S.Y.	\$1,610.00	110	\$177,100.00
12	533001	EMBEDDED GALVANIC ANODES	EACH	\$43.00	324	\$13,932.00
13	533003	REPLACEMENT REINFORCING BARS	LB	\$11.45	800	\$9,160.00
14	534020	EPOXY INJECTION	LF.	\$51.25	1390	\$71,237.50
15	540060	REINFORCING BARS GRADE 60	LB	\$5.40	1800	\$9,720.00
16	601000	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS	\$23,000.00	1	\$23,000.00
17	602200	GABIONS	C.Y.	\$635.00	123	\$78,105.00
18	603281	SWPPP PLAN PREPARATION AND MAINTENANCE	LS	\$14,000.00	1	\$14,000.00
19	604002	GEOTEXTILE CLASS 2	S.Y.	\$7.10	320	\$2,272.00
20	606001	SINGLE FACE W-BEAM GUARDRAIL	LF.	\$50.00	600	\$30,000.00
21	606051	END TREATMENT TL-3 END TERMINAL	EACH	\$4,800.00	4	\$19,200.00
22	606598	TCWS RETAINED BY THE CONTRACTOR	LF.	\$160.00	570	\$91,200.00
23	606599	RESETTING OF TCWB	LF.	\$10.25	410	\$4,202.50
24	613000	CLEANING CULVERTS AND DRAINAGE STRUCTURES	LS	\$15,000.00	1	\$15,000.00
25	618000	TRAFFIC CONTROL MANAGEMENT	LS	\$93,000.00	1	\$93,000.00
26	621000	MOBILIZATION	LS	\$112,000.00	1	\$112,000.00
27	701031	REMOVE AND RESET TRAFFIC SIGN	EACH	\$355.00	6	\$2,130.00
28	702810	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	LS	\$39,000.00	1	\$39,000.00
29	703002	OBJECT MARKER TYPE 2	EACH	\$92.75	8	\$742.00

30	704000	RETROREFLECTORIZED PAINTED MARKINGS 4"	LF.	\$1.10	5600	\$6,160.00
31	704099	TEMPORARY RETROREFLECTORIZED PAINTED MARKINGS 4"	LF.	\$0.95	5000	\$4,750.00
32	720060	VEHICULAR IMPACT ATTENUATOR UNIT - WORK ZONES	EACH	\$2,800.00	1	\$2,800.00
33	720110	REMOVE/RESET IMPACT ATTENUATOR UNIT	EACH	\$640.00	1	\$640.00
34	721000	REMOVAL OF PAVEMENT MARKING	LF.	\$0.95	5200	\$4,940.00
35	801000	CONSTRUCTION STAKING BY CONTRACTOR	LS	\$37,245.00	1	\$37,245.00
36	802000	POST CONSTRUCTION PLANS	LS	\$5,000.00	1	\$5,000.00

\$1,047,528.50

---

**TOTAL *exclusive of NM GRT***

**ALL BID ITEMS MUST BE EXCLUSIVE OF NMGR**