















## **SITE PLAN**

- New color sidewalks brick paving under east portal
- New stucco finished screen walls at existing electrical transformers
- New landscaping preserving some existing
   trees and plants street
   trees
- New parking lot paving, curbs & lighting with EV charging spaces & HCP spaces
- Restored courtyard & north enclosure wall with landscaping







## FIRST FLOOR PLAN

- Preserved corridors including original doors and decorative tin light fixtures
  restore painted wainscot
- Restored courtyard walls, windows, and preserving original glazed doors
- Restoring exterior porch and flanking banco's
- New elevator adjacent to corridor and main entrance via east portal
- Restoring original corridor brick paving exposing colors and patterns
- Providing accessible corridor between stepped floor levels
- Rehab office spaces with new finishes & code compliant energy saving MEP systems
- New fire alarms system and door access control





## SECOND FLOOR PLAN

- Preserved corridors including original doors and decorative tin light fixtures restore painted wainscot
- Restored courtyard walls with balconies and glazed balcony doors
- Providing accessible corridor with ramp between stepped floor levels
- Preserving commissioners chamber restore adjusting existing benching for ADA access
- Restoring required egress stair to courtyard with ADA area of refuge
- Adding complementary supplemental tin fixtures enhancing egress lighting
- Rehab office spaces with new finishes & code compliant energy saving MEP systems
- Preserving original judge's office and library at legal suite










### **EXTERIOR BUILDING ELEVATIONS**

- Preserving exterior massing, original features and details
- New cementitious stucco finish matching original stucco color
- East elevation restoring 3 decorative wood 2nd floor window header crowns and original window under portal at altered opening with exterior door – retain painted white walls & wainscot below portal
- West elevation replacing altered steel windows with new replica windows
- North elevation replacing altered steel clerestory windows at 2nd floor chamber with new replica windows and restoring the original courtyard site enclosure wall
- South elevation replacing numerous altered steel windows with new replica windows





# EXTERIOR RESTORED COURTYARD BUILDING ELEVATIONS

- 1st floor north facing elevation restored (possibly preserved tbd) porch with original courtyard entrance doors and restored flanking bancos; original window openings with replica wood hung windows; parapets
- 2nd floor north facing elevation restored balconies & railings; glazed balcony doors flanking preserved center balcony doors.
  Preserved decorative beams with stacked corbels & buttresses; restored parapets
- East facing elevation restored 2nd floor egress stair with accessible door to 1st floor below; original window openings with replica wood hung windows; parapets
- West facing elevation restored original window openings with replica wood hung windows; parapets

